

SECTION 708 RIGHT-OF-WAY MARKERS

MATERIAL		REFERENCE	PURP.	SAMPLED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
		TESTED BY		METHOD		CONTAINER	DISTR.			
RIGHT-OF-WAY MARKERS, PRECAST		708.02 708.03 Mat. Lab/ Const. Fab. Insp.	Accept.	Inspected, approved and stamped by Const. Fab. Insp. prior to use. See Section 805 - Precast Concrete (Nonprestressed Other Than Bridge Members) of this manual.			CD 1 & 6	-----	-----	Visual inspection by Proj. Engr.

I-77 5/99