

SECTION 802 STRUCTURAL EXCAVATION AND BACKFILL

MATERIAL		REFERENCE	PURP.	SAMPLED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
		TESTED BY		METHOD		CONTAINER	DISTR.			
BACKFILL	Reinforced Box Culverts	802.09(b) Proj. Engr.	Accept.	SEE SECTION 701 OF THIS MANUAL.						
	Structures Other Than Reinforced Box Culverts	802.09 Proj. Engr.	Accept.	-----	-----	-----	-----	-----	-----	Material shall be of acceptable quality and uniformly compacted by approved methods to the satisfaction of the Proj. Engr.
CONCRETE	Compressive Strength	802.09(e) Dist. Lab	*	Proj. Engr. S 301 TR 226	3 cyl/ location	2 ft ³ 6 in. x 12 in. cylinder mold	-----	-----	10 days	*Used to determine earliest date for placement of backfill next to structures.

I-128

8/02