SECTION 301 CLASS I BASE COURSE

		PURP.	SAMPLED BY	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING	
	MATERIAL		METHOD Diet Lab			CONTAINER	DISTR.		TIME	REMARKS
AGGREGATE BASES (DEDICATED STOCKPILE)	Blended Calcium Sulfate (BCS)	Prelim. Source Approval	Dist. Lab S 101	Mat. Lab	1/source/blend	6 full sample sacks			12 weeks	
		Quality Control	Contractor S 101	Contractor	*					*Must be controlled so that materials placed in stockpile will conform to specifications when tested by the Department.
		Design*	Proj. Engr. S 101	Dist. Lab	1/source	6 full sample sacks			4 days	Material must be source approved from an approved source. *For moisture-density relationships.
		Accept.	Proj. Engr. S 101	Dist. Lab	1/1000 yd ³	1 full sample sack			4 days	Material must be source approved from an approved source.
		IA	Dist. Lab S 101 or S 401	Dist. Lab		SI	EE INDEP	ENDENT ASSU	JRANCE PROG	RAM S 701.
	Recycled PC Concrete	Prelim. Source Approval	Dist. Lab S 101 & S 801	Mat. Lab	1/Stockpile*	12 full sample sacks				*See S 801 for maximum stockpile quantities. Raw material stockpiles shall be approved by Dist. Lab Engr. prior to crushing.
		Quality Control	Contractor S 101 & S 801	Contractor	*					*Must be controlled so that materials placed in stockpile will conform to specifications when tested by the Department.
		Design*	Proj. Engr. S 101	Dist. Lab	1/source	6 full sample sacks			4 days	Material must be source approved from an approved source. [AML] *For moisture-density relationships.
		Accept.	Proj. Engr. S 101	Dist. Lab	1/1000 yd ³	1 full sample sack			4 days	Material must be <u>from an approved</u> source approved. <u>(AML)</u>

Formatted	\/\/id	lth:	1//"

Formatted: Left

Commented [LC1]: Add test procedure

Commented [LC2]: Add "gradation"

Commented [LC3]: Same comments as for BCS

		IA	Dist. Lab S 101 or S 401	Dist. Lab		SE	EE INDEP	ENDENT ASSU	JRANCE PROC	GRAM S 701.
AGGREGATE BASES (DEDICATED STOCKPILE)	Stone	Quality Control	Contractor S 101	Contractor	*					*Must be controlled so that materials placed in stockpile will conform to specifications when tested by the Department.
(Cont'd)		Design*	Proj. Engr. S 101	Dist. Lab	1/source	6 full sample sacks			4 days	(QPL-2AML) *For moisture-density relationships.
		Accept.	Proj. Engr. S 101 S401	Dist. Lab	1/1000yd ³	1 full sample sack			4 days	(AML)
		IA	Dist. Lab S 101 or S 401	Dist. Lab		SE	EE INDEP	ENDENT ASSU	JRANCE PROC	GRAM S 701.
ASPHALTIC CONCRETE BASES		FOR	ALL RELATED	MATERIALS,	SEE SECTION 50	2 OF THIS MANUA	L. SEE IN	IDEPENDENT	ASSURANCE	PROGRAMS S 701.

SECTION 301 CLASS I BASE COURSE (Cont'd)

		MATERIAL	PURP.	SAMPLED BY	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
1-10	ASPHALTIC	Curing Membrane		METHOD			CONTAINER	DISTR.			
2/07	MATERIAL	-					SEE SECTION 50	06 OF THI	S MANUAL.		
		Prime Coat					SEE SECTION 50)5 OF THI	S MANUAL.		

1	Commented [LC4]: same
1	Formatted: Left

Commented [LC5]: remove "ic"

Formatted Table

Commented [LC6]: "ic"

CEMENT (HYDRAULIC)	Types I, II & IP	Prelim. Source Approval	Mfr. S 102	Mat. Lab	1/month/type	1 gal friction top can or acceptable moisture proof container				(QPL-7AML) Composited and blended from daily plant samples and submitted for quality control verification.
		Accept.		Proj. Engr.	1/shipment		CC 1 & 7			(QPL 7AML)
		Verif.	Proj. Engr. S 102	Mat. Lab	1/project/ source	1 gal friction top can			21 days	(QPL 7AML)
PORTLAND CEMENT CONCRETE BASES		Design/ Quality Control/ Accept.				SEE SECTIO	ON <mark>706</mark> & 9	001 OF THIS M	ANUAL.	
MIXTURE WITH CEMENT AT CENTRAL MIX PLANT sampling	Percent Cement	Quality Control	Contractor TR 436 S 401	Contractor TR 436	<u>1</u> 2/half day*					*In addition to start-up of plant each day and after each shut down.
f requency		Accept.	Proj. Engr. TR 436 S 401	Proj. Engr. TR-436	1/half day				1 hr	
	Gradation	Quality Control	Contractor S 101	Contractor	1/half day*	1 full sample sack				*When gradation is a requirement of specifications.
		Accept.	Proj. Engr. S 101	Proj. Engr.	1/day*	1 full sample sack			4 hr.	*Gradation will be run when questionable or individual components of Sand-Clay-Gravel are mixed in a pugmill.
	Moisture Content	Quality Control	Contractor S 101 S 401	Contractor TR-403	1/half day*					*In addition to start-up of plant each day and after each shut down.
		Accept.	Proj. Engr. S 101	<u>Proj.</u> <u>Engr.</u>	<u>1 / half day</u>					-10-10-

Commented [A7]: Is 706 the correct reference? 7-26-19 – Removed 706

Commented [JD8]: Is S 401 correct? Should it be S 301?

Commented [JD9]: What procedure? S 102 or S 301?

Commented [JD10]: Is S 401 correct? Should it be S 301?

Formatted: Centered

Proportions	Quality Control	Contractor TR 436 S 401	Contractor TR 436	*	 	 	*Shall be monitored continuously.
	Accept.	Contractor TR 436 S 401	Proj. Engr. TR-436	1/half day	 	 1 hr.	
Pulverization	Quality Control	Contractor S 401	Contractor TR-434	1/half day	 	 	
	Accept.	Proj. Engr. S 401	Proj. Engr. TR-434	1/half day	 	 1/2 hr.	

SECTION 301 CLASS I BASE COURSE (Cont'd)

		MATERIAL	PURP.	SAMPLED BY	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	DEMBKO
		MATERIAL		METHOD			CONTAINER	DISTR.			REMARKS
	BASE MATERIAL ON ROADWAY	Density	Quality Control	Contractor TR 401 S 101 or S 401	Contractor TR 404	*					*Shall test sufficient to ensure specifications will be met.
I-12 2/07			Accept.	Proj. Engr. TR 401 S 101 or S 401	Proj. Engr. TR-404	1/1000 lin ft/ 2-lane rdwy or 1/2000 lin ft/shoulder		-		1/2 hr.	* Asphalt concrete base course will be accepted in accordance with Section 502.
			IA	Dist. Lab TR 401 S 101 or S 401	Dist. Lab TR 401		SE	EE INDEPI	ENDENT ASSU	RANCE PROG	RAM S 701.
		Cross Slope & Grade	Quality Control	Contractor	Contractor	*					*Shall take measurements sufficient to ensure specifications are met.

Formatted: Left

		Accept.	Proj. Engr.	Proj. Engr.	1/half day				1/4 hr.	Use an approved 10-ft metal static straightedge or other approved device.
	Moisture Content (For Soil Cement or Cement	Quality Control	Contractor TR 403 S 101 S 401	Contractor TR-403	*					*Shall test sufficient to ensure specifications are met.
	Stabilized Mixtures)	Accept.	Proj. Engr. S 101 S 401	Proj. Engr. TR-403	1/half day				1 hr.	(TR 403)
	Thickness & Width	Quality Control	Contractor	Contractor TR-602	*					*Shall take measurements sufficient to ensure specifications are met.
		Verif.	Proj. Engr. TR 602	Proj. Engr. TR-602	1/half day				1/4 hr.	Proj. Engr. shall notify the Dist. Lab when section is complete.
		Accept.	Dist. Lab TR 602	Dist. Lab TR-602	1/1000 lin ft/ 2-lane rdwy or 1/2000 lin ft/shoulder			300 lin ft per location	3 days	*See DOTD TR 602. For small quantity, Proj. Engr. Documents in field book.
SOIL (RAW)	Dedicated	Quality Control	Contractor	Contractor						Control uniformity of moisture and soil type
	Stockpile	Quality Control	S 401							while stockpile is being built.
		Design*/ Accept.	Proj. Engr. S 401	Dist. Lab	1/1000 yd ³	6 full sample sacks**			21 days max	*For cement content & moisture-density relationships. **When soils are to be blended, each component must meet specifications before blending. Design and final acceptance will be conducted on the blend.
		IA	Dist. Lab S 401	Dist. Lab		SE	E INDEP	ENDENT ASSU	RANCE PROG	GRAM S 701.
WATER		Accept.	Proj. Engr. S 303	Mat. Lab	1/source*	1 qt plastic bottle			21 days	*Drinkable water need not be sampled.

SECTION 302 CLASS II BASE COURSE

Formatted: Highlight

		PURP.	SAMPLED BY	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING	
	MATERIAL		METHOD			CONTAINER	DISTR.		TIME	REMARKS
	NOTE: WHEN	A CLASS II BAS	E COURSE IS	PRODUCED B	Y CENTRAL PLAN	T MIXING, USE TH	E SAMPL	ING SCHEDUL	ES IN SECTIO	N 301 OF THIS MANUAL.
AGGREGATE BASES	Blended Calcium Sufate (BCS)	Prelim. Source Approval	Dist. Lab S 101	Mat. Lab	1/source/blend	6 full sample sacks			12 weeks	
		Quality Control	Contractor S 101	Contractor	*					*Must be controlled so that materials placed in stockpile will conform to specifications when tested by the Department.
		Design*	Proj. Engr. S 101	Dist. Lab	1/source	6 full sample sacks			4 days	Material must be source approved/rom an approved source. *For moisture-density relationships.
		Accept.	Proj. Engr. S 101	Dist. Lab <u>TR 122</u> <u>TR 113</u>	1/1000 yd ³	1 full sample sack			4 days	Material must be source approvedfrom an approved source.
		IA	Dist. Lab S 101 or S 401	Dist. Lab <u>TR 122</u> <u>TR 113</u>		SE	E INDEP	ENDENT ASSU	JRANCE PROG	RAM S 701.
	Recycled PC Concrete	Prelim. Source Approval	Dist. Lab S 801	Mat. Lab	1/stockpile*	6 full sample sacks			5 weeks	*See S 801 for maximum stockpile quantities. Raw material stockpiles shall be approved by Dist. Lab Engineer prior to crushing.
		Quality Control	Contractor S 101	Contractor	*					*Must test sufficient to ensure materials being delivered meet specification requirements.
		Design*	Proj. Engr. S 101	Dist. Lab	1/source	6 full sample sacks			4 days	Material must be source approved from an approved source. *For moisture-density relationships.
		Accept.	Dist. Lab S 101	Dist. Lab	1/1000 yd ³	1 full sample sack		100 yd ³	4 days	Material must be source approved from an approved source.

Commented [LC11]: Apply comments for 301 to 302

Formatted: Pattern: Clear (Accent 1)

	Stone	Quality Control	Contractor S 101	Contractor	*					*Must be controlled so that materials placed in stockpile will conform to specifications when tested by the Departmenttest sufficient to ansure materials being delivered meet specification requirements.
		Design*	Proj. Engr. S 101	Dist. Lab	1/source	6 full sample sacks			4 days	(QPL-2AML) *For moisture-density relationships.
		Accept.	Dist. Lab S 101	Dist. Lab	1/1000 yd ³	1 full sample sack		100 yd ³	4 days	(QPL-2AML) Materials must be source approved from an approved source.
		IA	Dist. Lab S 101	Dist. Lab		SE	EE INDEP	ENDENT ASSU	IRANCE PRO	GRAM S 701.
ASPHALTIC CONCRETE BASES		'	FOR ALI	L MATERIALS,	SEE 502 OF THIS	MANUAL. SEE-IN	DEPEND	ENT ASSURAN	ICE PROGRA	M.S.701.

SECTION 302 CLASS II BASE COURSE (cont'd)

_	N	MATERIAL	PURP.	SAMPLED BY METHOD	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
15	ASPHALTIC MATERIALS	Curing Membrane					SEE SECTION 50	06 OF THIS	S MANUAL.		
		Prime Coat					SEE SECTION 5	05 OF THIS	S MANUAL.		

CEMENT (Hydraulic)	Types I, II & IP	Prelim. Source Approval	Mfr. AASHTO T-127	Mat. Lab AASHTO T.127	1/month/type	1 gal friction top can or acceptable moisture proof container				(QPL-7AML) Composited and blended from daily plant samples and submitted for quality control verification.
		Accept.		Proj. Engr.	1/shipment		CC 1 & 7			(QPL 7AML)
		Verif.	Proj. Engr. S 101	Mat. Lab	1/project/ source	1 gal friction top can			21 days	(QPL-7AML)
CONCRETE, PORTLAND CEMENT, BASE		Design/ Quality Control/ Accept.				SEE SEC	TION 901	OF THIS MANU	JAL.	

SECTION 302 CLASS II BASE COURSE (cont'd)

	MATERIAL	PURP.	SAMPLED BY	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
'	WATERIAL		METHOD			CONTAINER	DISTR.			REWARKS
MIXTURE WITH CEMENT AT CENTRAL MIX						SEE SEC	TION 301	OF THIS MAN	UAL.	
BASE MATERIAL ON ROADWAY	Rate (For soil cement or cement treated bases	Quality Control	Contractor TR-436	Contractor TR-436	each transport*					*The contractor shall determine the length of spread prior to mixing. Use an approved sampling device.
	only)	Accept.	Proj. Engr. TR 436	Proj. Engr. TR 436	1/day*					*The Proj. Engr. will verify the length of spread on first transport prior to mixing and total spread for the day. At the discretion of the Proj. Engr. Additional testing shall be performed when cement content changes. Use an approved sampling device.

Formatted: Centered

Commented [A12]: Les Fletcher's suggestion to verify the 1st transport to assure that personnel spreading transports are competent.

Cross Slope & Grade	Quality Control	Contractor	Contractor	*					*Shall check sufficient to ensure specifications are met.
	Accept.	Proj. Engr.	Proj. Engr.	1/half day				1/4 hr.	Use an approved 10 ft metal static straightedge or other approved device.
Density	Quality Control	Contractor TR 401	Contractor TR.401	*					*Shall test sufficient to ensure specifications are met.
	Accept.	Proj. Engr. TR-401	Proj. Engr. TR-401	1/1000 lin ft/ 2-lane rdwy or 1/2000 lin ft/shoulder				1/2 hr.	
	IA	Dist. Lab TR 401	Dist. Lab		SE	EE INDEPI	ENDENT ASSU	JRANCE PROG	GRAM S 701.
Moisture Content (For Soil Cement or treated Sand- Clay-Gravel only)	Quality Control	Contractor S 101 or S 401	Contractor	*					*Shall test sufficient to ensure specifications are met.
	Accept.	Proj. Engr. S 101 or S 401	Proj. Engr.	1/1000 lin ft/ 2-lane rdwy or 1/2000 lin ft/shoulder	1 gal friction top can*			1 hr.	*May be obtained by M.C. % determined during application of TR 415 B, if available on in-place moisture at the time of compaction (TR 403).
Pulverization (For soil-cement only)	Quality Control	Contractor S 401	Contractor	*					*Soil cement shall be tested sufficiently to ensure specifications are met.
	Accept.	Proj. Engr. S 401	Proj. Engr.	1/1000 lin ft/ 2-lane rdwy or 1/2000 lin ft/shoulder	1 gal friction top can			1/2 hr.	DOTD-TR-431
Thickness & Width	Quality Control	Contractor	Contractor	*					*Shall be measured sufficiently to ensure specifications are met.

Formatted: Centered

Verif.	Proj. Engr. TR 602	Proj. Engr. <u>TR-602</u>	1/half day	 		1/4 hr.	Proj. Engr. To notify Dist. Lab when section is completed.
Accept.	Dist. Lab	Dist. Lab	1/1000 lin ft/ 2-lane rdwy or 1/2000 lin ft/shoulder		300 lin ft per location		See DOTD TR 602. For small quantity, Proj. Engr. documents in field book.

SECTION 302 CLASS II BASE COURSE (cont'd)

		MATERIAL	PURP.	SAMPLED BY METHOD	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
	GEOTEXTILE SEPARATOR FABRIC	Class D	Accept.	SEE SECTION 203 OF THIS MANUAL.	Mat. Lab						Only required when aggregate base course placed on un treated or lime treated soils.
16	SOILS (RAW) ON ROADWAY FOR SOIL CEMENT	Density (120%)	Quality Control	Contractor TR 401 S 401	Contractor TR-401	*					*Shall test sufficient to ensure specifications are met. Minimum density is required on roadway prior to spreading cement. Check M.C. % before mixing with cement (TR 403).
			Accept.	Proj. Engr. TR-S_401	Proj. Engr. TR 401	1/half day				1/2 hr.	
		Soils/Soil- Aggregate	Design*	Proj. Engr. S 101 or S 401	Dist. Lab	1/1000 lin ft/2-lane rdwy or 1/ 2000 lin ft/shoulder	6 full sample sacks of blend			21 days	*For cement content and moisture-density relationships. Design will be conducted on blend.

Commented [LC13]: We probably shouldn't put spec here. This will show on the typical section

Commented [LC14]: Not sure if we should put spec here

		Accept.	Proj. Engr. S 101 or S 401	Dist. Lab	1/1000 lin ft/2-lane rdwy or 1/ 2000 lin ft/shoulder	1 full sample sack of blend & 1 sample sack of each component		200 lin ft	5 days	Blending of soils prior to mixing with cement will not be allowed for adjustment of LL or PI.
		IA	Dist. Lab S 101 or S 401	Dist. Lab		SE	E INDEP	ENDENT ASSU	RANCE PROG	GRAM S 701.
SOILS (RAW) IN STOCKPILE FOR SOIL CEMENT	Soils/Soil- Aggregate	Quality Control	Contractor S 101 or S 401	Contractor	*					*Shall test sufficient to ensure specifications will be met when placed on roadway. Check M.C. % before spreading cement.
		Design*	Proj. Engr. S 101 or S 401	Dist. Lab	1/1000 yd ³	6 full sample sacks of blend & 1 full sample sack of each component			21 days	*For cement content and moisture-density relationships. Design will be conducted on blend. For contractor design material sample must be accompanied by independent lab result in accordance with specification.
		Accept.	Proj. Engr. S 101 or S 401	Dist. Lab	1/1000yd ³	1 full sample sack of blend & 1 full sample sack of each component		100 yd ³	5 days	Blending of soils prior to mixing with cement will not be allowed for adjustment of LL or PI.
		IA	Dist. Lab S 101 or S 401	Dist. Lab		SE	E INDEP	ENDENT ASSU	RANCE PROG	SRAM S 701.
Water		Accept.	Proj. Engr. S 303	Mat. Lab	1/source*	1 qt plastic bottle			21 days	*Drinkable water need not be sampled.

SECTION 303 IN-PLACE CEMENT STABILIZED BASE COURSE & IN-PLACE CEMENT TREATED BASE COURSE

					· · · · · · · · · · · · · · · · · · ·					
		PURP.	SAMPLED BY	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	
'	MATERIAL		METHOD			CONTAINER	DISTR.			REMARKS
FOR DETAILS ON										REFER TO SECTION 506 OF THIS MANUAL. JAL, AS APPLICABLE.
MATERIAL FOR BASE PRIOR TO SPREADING CEMENT (Existing or Furnished	Contractor Furnished Soil	Quality Control	Contractor S 101 or S 401	Contractor						Must test sufficient to ensure material will meet specification requirements before placing on roadway. Check M.C.% on all materials before spreading cement.
or Furnished Soils/Soil- Aggregate)		Accept.	Proj. Engr. S 101 or S 401	Dist. Lab	1/1000 yd ³	1 full sample sack			4 days	Contractor furnished material will be approved before incorporation into existing material. Furnished material not meeting the requirement of specification Subsection 302.02(a) will not be incorporated in the base.
	Density (93%)	Quality Control	Contractor TR 401 S 401	Contractor TR 401	*					*Shall be tested frequently enough to ensure specifications are met. Minimum density is required on roadway prior to mixture with cement. All blending of soils materials will be accomplished before testing.
		Accept.	Proj. Engr. TR-S_401	Proj. Engr. TR 401	1/half day				1/2 hr.	
	In-Place Material on Roadway	Design*/ Accept.	Contractor S101 or S401	Dist. Lab	1/1000 lin ft/2-lane rdwy or 1/2000 lin ft/ shoulder	6 full sample sacks			14 days	*For cement content and moisture-density relationships (if needed). Design will be conducted on the final blend.
	Pulverization	Quality Control	Contractor TR 401	Contractor TR 401	*					*Shall be tested frequently enough to ensure specifications are met.
		Accept.	Proj. Engr. TR 431	Proj. Engr. TR 431	1/1000 lin ft/2-lane rdwy or 1/2000 lin ft/ shoulder				1/2 hr.	Shall be obtained after blending of any contractor furnished material. Pulverization shall be approved prior to spreading cement.

1-17 2/07

SECTION 303 IN-PLACE CEMENT STABILIZED BASE COURSE & IN-PLACE CEMENT TREATED BASE COURSE (Cont'd)

	MATERIAL	PURP.	SAMPLED BY	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
	MATERIAL		METHOD			CONTAINER	DISTR.			KEMPARIO
FOR DETAILS O										REFER TO SECTION 506 OF THIS MANUAL. NUAL, AS APPLICABLE.
MIXTURE WITH CEMENT ON ROADWAY	Cement Spread Rate	Quality Control	Contractor* TR 436	303.07 Contractor TR 436	each transport	**				*The contractor shall determine the length of spread prior to mixing. **Use an approved sampling device.
		Accept.	Proj. Engr.* TR 436	Proj. Engr. TR 436	1/day	**			1/2 hr.	*The Proj. Engr. will verify the length of spread on first transport prior to mixing and total spread for the day. **Use an approved sampling device.
	Cross Slope & Grade	Quality Control	Contractor	303.07 Contractor	*					*Shall test sufficient to ensure specifications are met. Use an approved 10 ft metal static straightedge.
		Verif.	Proj. Engr.	Proj. Engr.	≛ <u>1 / half-day</u>				-	Use an approved 10 ft. metal static straightedge or other approved device.
	Density	Quality Control	Contractor TR 401	303.07 Contractor TR 404	*					*Shall test sufficient to ensure specifications are met.
		Accept.	Proj. Engr. TR 401	Proj. Engr. TR-401	1/1000 lin ft/2-lane rdwy or 1/2000 lin ft/ shoulder				1/2 hr.	
		IA	Dist. Lab	303.11 Dist. Lab TR 401		S	EE INDEP	ENDENT ASSU	JRANCE PROG	RAM S 701.

Moisture Content	Quality Control	Contractor S 101 or S 401	303.05 303.07 Contractor	*		 		*Shall test sufficient to ensure specifications are met. (DOTD TR 403)
	Accept.	Proj. Engr. S 101 or S 401	Proj. Engr.	1/1000 lin ft/2-lane rdwy or 1/2000 lin ft/ shoulder	1 gal friction top can*	 		*May be obtained by M.C.% determined during application of TR 415 B, if available on in-place moisture at the time of compaction (TR 403).
Pulverization	Accept.	<u>Proj. Engr.</u> <u>S 101 or</u> <u>S 401</u>	Proj. Engr.	1/1000 lin ft/2-lane rdwy or 1/2000 lin ft/ shoulder	<u></u>	 	<u>1/2 hr.</u>	
Thickness & Width	Quality Control	Contractor	303.07 Contractor	*		 		*Shall be measured sufficiently to ensure specifications are met.
	Verif.	Proj. Engr. TR 602	Proj. Engr. TR 602	1/half day		 		Proj. Engr. shall notify Dist. Lab when section is complete.
	Accept.	Dist. Lab TR-602	Dist. Lab TR-602	1/1000 lin ft/2-lane rdwy or 1/2000 lin ft/ shoulder		 300 lin ft per location	3 days	*See DOTD TR 602. For small quantity, Proj. Engr. documents in field book.

SECTION 304 LIME TREATMENT

MATERIAL	PURP.	SAMPLED BY	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	DEMARKS
MATERIAL		METHOD			CONTAINER	DISTR.			REMARKS

FOR DETAILS ON HYDRAULIC CEMENT REFER TO SECTION 301 OF THIS MANUAL. FOR DETAILS ON ASPHALTIC CURING MEMBRANE, REFER TO SECTION 506 OF THIS MANUAL. FOR DETAILS ON ASPHALTIC CONCRETE OR PORTLAND CEMENT CONCRETE, REFER TO SECTIONS 502 AND 901 OF THIS MANUAL, AS APPLICABLE.

CURING MEMBRANE	Type B (only)			Mat. Lab/ Proj. Engr.			SEE	SECTION 506	OF THIS MAN	UAL.
LIME (Hydrated and Quicklime)		Prelim. Source Approval	Mfr. S 102	Mat. Lab	1/quarter					
		Accept.		Mat. Lab	1/shipment		CD 1 & 7			(QPL 34AML)
		Verif.	Proj. Engr. S 102	Mat. Lab	1/project/ source	1 gal friction top can			21 days	(QPL 34AML) *Not required if sampled under another item.
MIXTURE ON ROADWAY	Density- (Type B & C)	Quality Control	Contractor TR 401	Contractor IR-401	*					*Shall check sufficient to ensure specifications are met.
		Accept.	Proj. Engr. TR 401	Proj. Engr. TR-401	1/1000 lin ft/2-lane rdwy or 1/2000 lin ft/ shoulder				1/2 hr.	
		IA (Type B only)	Dist. Lab	Dist. Lab		SE	E INDEP	ENDENT ASSU	JRANCE PROC	GRAM S 701.
	Density-(Type D)	Accept.	Proj. Engr.	Proj. Engr.						Compact to the satisfaction of the Engineer.
	Density- (Type E)	Accept.	Proj. Engr.	Proj. Engr.			SEE	SECTION 203	OF THIS MAN	UAL.
	Lime Spread Rate	Quality Control	Contractor* TR 436	Contractor	Each transport	**			1/2 hr.	*The contractor shall determine the length of spread. **Use an approved sampling device

	Accept.	Proj. Engr.*	Proj. Engr.	1/1000 lin ft/2-lane	**	 	1/2 hr.	*_The Proj. Engr. shall verify the length of
		TR 436	TR-436	rdwy or 1/2000 lin				spread.
				ft/ shoulder 1 / day				**Use an approved sampling device.
				,				

SECTION 304 LIME TREATMENT (Cont'd)

		PURP.	SAMPLED BY	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	
	MATERIAL		METHOD			CONTAINER	DISTR.			REMARKS
MIXTURE ON ROADWAY (Cont'd)	Maximum Dry Density	Quality Control	Contractor S 101	Contractor	*	the whole			**************************************	Shall Check sufficient to ensure specifications are met.
		Accept.	Proj. Engr. S 101	<u>Proj. Engr.</u>	*	<u> </u>		*****	****	1 For Type B, determine optimum moisture in accordance with TR 403.
	Pulverization (Type B & C)	Quality Control	Contractor S 101	Contractor	*					*Shall Check sufficient to ensure specifications are met.
00000		Accept.	Proj. Engr. S 101	Proj. Engr.	1/1000 lin ft/2-lane rdwy or 1/2000 lin ft/ shoulder	1 gal friction top can			1/2 hr.	
	Pulverization (Type D & E)	Accept.	Proj. Engr	<u>Proj. Engr.</u>		*				*Satisfaction of Engineer.
	Thickness & Width (Type B)	Quality Control	Contractor	Contractor	*					*Shall Check sufficient to ensure specifications are met.
		Verif.	Proj. Engr. TR 602	Proj. Engr. TR-602	1/half day					Proj. Engr. to notify Dist. Lab when section is complete.

Commented [A15]: Per Les Fletcher, amount of material a transport carries and the field dimensions vary. Verifying total spread for the day makes more sense.

		Accept.	Dist. Lab TR 602	Dist. Lab TR-602	1/1000 lin ft/2-lane rdwy or 1/2000 lin ft/ shoulder			300 lin ft per location	3 days	See DOTD TR 602. For small quantity, Proj. Engr. Documents in field book.
	Thickness & Width (Type C & D)	Accept.	Proj. Engr. TR 602*	Proj. Engr. <u>TR-602*</u>	*					*Satisfaction of the Project Engr. Documents in field book.
	Thickness & Width (Type E)	Accept.	Proj. Engr	Proj. Engr.		FOR LIFT THIC	KNESS R	REQUIREMENT	S SEE SECTIO	N 203 OF THIS MANUAL
SOIL OR SOIL- AGGREGATE	% Lime*	Design	Proj. Engr. S 101 or S 401	Dist. Lab	1/1000 lin ft/2-lane rdwy or 1/2000 lin ft/ shoulder	6 full sample sacks			10 days	*Not required when percent lime is specified in plans or project specifications.
Water		Accept.	Proj. Engr. S 303	Mat Lab	1/source*	1 qt plastic bottle			21 days	*Drinkable water need not be sampled.

SECTION 305 SUBGRADE LAYER

	MATERIAL	PURP.	SAMPLED BY METHOD	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT. DISTR.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
NOTE: WHEN A	SUBGRADE LAY	ER IS PRODUCE	ED BY CENTRA		ING, USE THE SAN TO APPLICABLE S				THIS MANUAL	. FOR PLACEMENT AND CONSTRUCTION
AGGREGATES	Stone, Recycled PC Concrete	SEE SECTION MAN		Dist. Lab						
	Asphaltic Concrete	Prelim. Source Approval	Dist. Lab S 101	Mat Lab	1/source/blend	6 full sample sacks			4 weeks	Source shall be approved by Materials Lab prior to use.

Formatted: Font: Not Bold

	Blended Calcium Sulfate					SEE SECTION 30)2 OF THI	S MANUAL.		
		Quality Control	Contractor S-101	Contractor	<u>*</u>					*Must test sufficient to ensure materials being delivered meet specification requirements.
		Design*	Proj. Engr. S 101	-Diet. Lab	1/source	6 full sample sacks		*****	4 days	For moisture-density relationships-
		Accept.*	Proj. Engr. S 101	-	1/1000 yd³	1 full sample sack		100 yd ³	4 days	"Shall not be placed within 10 ft of metal pipe. Shall be from an approved source.
CEMENT					SEE SE	CTION 302 OF TH	IS MANU	AL.		
ASPHALTIC MATERIALS	Curing Membrane					SEE SECTION 50	06 OF THI	S MANUAL.		
	Prime Coat					SEE SECTION 50	5 OF THI	S MANUAL.		
GEOTEXTILE FABRIC					SEE SE	CTION 203 OF TH	IS MANU	AL		
LIME (Hydrated or Quicklime)					SEE SE	CTION 304 OF TH	IS MANU	AL.		
MIXTURE WITH LIME AND/OR CEMENT ON ROADWAY	Pulverization*	Accept.	Proj. Engr. S 401	Proj. Engr.	1/1000 lin ft/2-lane rdwy or 1/2000 lin ft/shoulder				1/2 hr.	*For soil after mixing with cement and/or lime.
SOIL		Design*	Proj. Engr. S 401	Dist. Lab.	1/1000 lin ft/2-lane rdwy or 1/2000 lin ft/shoulder	6 full sample sacks			10 days	*For Moisture Density relationships.

Formatted: Centered

Commented [LC16]: Ic – do a search throughout

Ac	Accept.* Proj. Engr. Dist. La	1/1000 lin ft/2-lane rdwy or 1/2000 lin ft/shoulder		*When soils are to be blended, each component must meet specifications before blending. Design and final acceptance will be conducted on the blend.
----	-------------------------------	---	--	---

SECTION 305 SUBGRADE LAYER (Cont'd)

		MATERIAL	PURP.	SAMPLED BY	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
<u></u>				METHOD			CONTAINER	DISTR.			
	SUBGRADE AYER	Density (Stone Recycled PCC, Soil Cement)				SEE	E SECTIONS 302 A	ND 308-0	F THIS MANU	AL	
1-22		Density (Blended Calcium Sulfate)	Quality Control	Contractor S 401	Contractor	*					*Shall check sufficiently to ensure specifications requirements.
2/07			Accept.	Proj. Engr. S 401	Dist. Lab	1/1000 lin ft/ 2-lane rdwy or 1/2000 lin ft/ shoulder				1/2 hr.	Shall not be placed within 10 ft of metal pipe. Shall be from an approved source.
		Thickness & Width	Verif.	Proj. Engr. TR 602	See Sect	tion 302, 303 or 304	of this Manual as	applicab	le. District Lal	o not required t	to perform DOTD TR 602 Measurements.
	VATER		Accept.	Proj. Engr. S 303	Mat. Lab	1/source	1 qt plastic bottle			21 days	Drinkable water need not be sampled.

SECTION 306 SCARIFYING & COMPACTING ROADBED

I-23	MATERIAL	PURP.	SAMPLED BY	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY		REMARKS	ĺ
------	----------	-------	---------------	--------------	------------	-------------	-------	-------------------	--	---------	---

			METHOD			CONTAINER	DISTR.		TYPICAL HANDLING TIME	
EXISTING MATERIAL	Density	Accept.	Proj. Engr. TR 401, TR 415 or TR 418	Proj. Engr TR 401. TR 415 or TR 418	1/1000 lin ft/ 2-lane rdwy or 1/2000 lin ft/ shoulder				1/2 hr.	
ASPHALTIC MATERIAL	Prime Coat				s	SEE SECTION 596	- <u>505</u> ТО Т	HIS MANUAL.		

SECTION 307 PERMEABLE BASES

	N	MATERIAL	PURP.	SAMPLED BY METHOD	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	REI	MARKS
	AGGREGATE	Stone	Accept.	Proj. Engr. S 101	Dist. Lab	1/1000yd3	1 full sample sack			4 days	(QPL 2AML)	
	ASPHALTIC MATERIALS	Asphalt Cement	Prelim. Source Approval, Accept., Verif.			SEE SECTION	N 502 OF THIS MAI	NUAL			(QPL 41<u>AML</u>)	
2/07	ANTI-STRIP		Prelim. Source Approval, Accept. Verif.			SEE SECTION	N 502 OF THIS MAI	NUAL			(QPL 57AML)	
	ADMIXTURE		Prelim. Source Approval, Accept., Verif.			SEE SECTION	N 901 OF THIS MAI	NUAL			(QPL 58 AML)	
	CEMENT HYDRAULIC)		Prelim. Source Approval, Accept., Verif.			SEE SECTION	N 901 OF THIS MAI	NUAL			(QPL-7AML)	

Commented [LC17]: To get a density, you will first need a Proctor

CURING COMPOUND		Prelim. Source Approval, Accept.			SEE SECTIO	N 601 OF THIS MA	NUAL			(QPL 65 AML)		
PERMEABLE ASPHALT BASE (PLANT)					SEE SI	ECTION 502 OF TH	<u>IIS MANU</u>	AL.			Fo	rma
	AME	Design*	Parameter.	Contractor	4/mix/plant					"Contractor shall submit to the Dist. Lab Engr. The proposed job mix formula with supporting design data. Approvel is required prior to starting work.	Fo	rma
		Verif.*	Proj. Engr. S101, S201, S601	Dist. Lab	4/JME					*Dist. Lab verifies % retained coating in accordance with TR-317.		
	Anti-Strip-Additive	Accept.	Proj. Engr. S-605	Proj. Engr.	1/2500 tons	<u></u>				±%-AS-from-meter.	Fo	rma
	Asphalt Coment	Accept.	Proj. Engr. S-605	Proj. Engr.	1/2500 tons	<u>.</u>				±%-AC-from-motor-	Fo	rma
	Loose Mixture (Gradation, % AG, & % Gruphed)	Quality Centrol	Contractor S 203 & S 605	Contractor	1/4000 tons	suitable sampling bucket					Fo	rma
		Vorif.	Proj. Engr. S-203	Dist. Lab	1/5000 tons	1 gal friction top			3 days			
	1	1			SECTION 307 P	ERMEABLE BASE	:S			I		

		ATERIAL	PURP.	SAMPLED BY	TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	DEMARKS
1-25 2/		ATERIAL		METHOD			CONTAINER	DISTR.			REMARKS
	PERMEABLE A CONCRETE BASE (PLANT)	Mix Design	Design/ Accept.	*	-Contractor/ Dist. Lab	1/mix/plant	*******				*Contractor shall submit to the Dist. Lab Engr. the proposed job mix formula with supporting data. Approval is required prior to starting work.

Formatted: Centered

Formatted: Highlight

Formatted: Highlight

natted: Highlight

Formatted: Highlight

						SEE SECTION 90)1 OF THI	S MANUAL.		
		Verif.	*	Proj. Engr.	1/truck					"Obtain "batch tickets" to verify quantities from mix design.
PERMEABLE BASES	Cross Slope & Grade	Quality Control	Contractor	Contractor	*					Shall measure sufficiently to ensure specifications are met. Under thickness shall not exceed 4/2" (42 mm).
		Accept.	Proj. Engr.*	Proj. Engr.	1/day					*Use 10 ft metal static straight edge or approved device.
	Thickness & Width	Quality Control	Contractor	Contractor	*					*Shall measure sufficiently to ensure specifications are met.
		Accept.	Contractor/ Proj. Engr. TR602	Proj. Engr. TR602	1/2000 lin ft					Under thickness shall not exceed 1/2" (12 mm).
	Temperature	Accept.*	Proj. Engr. S 605	Proj. Engr.	1/5000 tons					*Required for Asphaltic Concrete only.
WATER		Accept.	Proj. Engr. S 303		1/source*	1 qt plastic bottle			21 days	*Drinkable water need not be sampled.

MATERIAL	PURP. SAMPLED BY		TESTED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	
	METI	METHOD			CONTAINER	DISTR.			REMARKS

NOTE: WHEN A SUBGRADE LAYER IS PRODUCED BY CENTRAL PLANT MIXING, USE THE SAMPLING SCHEDULES IN SECTION 301 OF THIS MANUAL. FOR PLACEMENT AND CONSTRUCTION REFER TO APPLICABLE SECTIONS OF THIS MANUAL.

Formatted: Centered

Formatted Table

SECTION 309 IN-PLACE CEMENT TREATED SUBGRADE

PURP. SAMPLED **TESTED** MIN. MIN. QUANT. CERT. SMALL TYPICAL BY BY FREQ. QUANTITY HANDLING TIME MATERIAL REMARKS METHOD CONTAINER DISTR. CEMENT SEE SECTION 302 OF THIS MANUAL. Proj. Engr. <u>S 101 or</u> <u>S 401</u> **EMENT RATE** % Cement* Design Dist. Lab 21 days Not required when percent cement is specific Proj. Engr. Design* Dist. Lab. /1000 lin ft/2-lane 6 full sample 10 days For Moisture Density relationships. ____ ____ S 401 rdwy or 1/2000 <u>sacks</u> lin ft/shoulder Contractor* each transport The contractor shall determine the length of pread prior to mixing. 1-22 2/07 Use an approved sampling device. Proj. Engr.* Proj. Engr. 1/day The Proj. Engr. will verify the length of spread Accept. on first transport prior to mixing and total sprea or the day. Use an approved sampling device. ulverization Contractor <u>S 101</u> are met. Proj. Engr. Proj. Engr. /1000 lin ft/2-lane 1 gal friction top <u>1/2 hr.</u> Accept. S 101 <u>can</u> ft/ shoulder Contractor Contractor Shall check sufficient to ensure specification Proj. Engr. Compact to the satisfaction of the Engineer. Accept.

	<u>Thickness &</u> <u>Width</u>	<u>Verif.</u>	<u>Proj. Engr.</u>	Proj. Engr.	# 17	mar at another	<u></u>	 	Satisfaction of the Project Engr. Documents in field book.
WATER		Accept.	Proj. Engr. S 303	Mat. Lab	1/source	1 qt plastic bottle		 21 days	Drinkable water need not be sampled.

Formatted: Left