MATERIAL		REFERENCE TESTED BY	PURP.	SAMPLED BY METHOD	MIN. FREQ.	MIN. QUANT. CONTAINER	CERT. DISTR.	SMALL	TYPICAL HANDLING TIME	REMARKS
AGGREGATES	Rate of Application	507.06(b) Contractor	Quality Control	Contractor	Prior to first pass of aggregate spreader*					*Must check sufficient to ensure materials being applied meet specification requirements.
		507.06(b) Proj. Engr.	Accept.	Proj. Engr.	First pass of aggregate spreader*				1 day	*Must check sufficient to ensure materials being applied meet specification requirements.
	Size 1, 2, 3	507.02 1003.05 Dist. Lab	Accept.	Proj. Engr. S 101	1/1000 yd³/ size	1 full sample sack		2,000 yd²	5 days	(QPL 2)
ASPHALTIC	Emulsified Asphalt	1002.01 Mat. Lab	Prelim. Source Approval	Refinery S 201	1/storage tank	1 gal Plastic bottle	CA 7		5 days	(QPL 41) Non Self Certified Must have tank approved by Mat. Lab prior to shipping whenever asphalt cement is added or modified.
		1002.01 Refinery	Prelim Source Approval	Refinery S 201	1/Supplier tank whenever asphalt is added to a tank or modified*	2 - 1 gal Plastic bottles	CA 7		2 hrs. during working hours	(QPL 41) Self Certified *Supplier, shall sample and test each tank in accordance with quality control plan whenever asphalt cement is added or modified and supply CA to Mat. Lab along with 1 qt sample for verification testing.
		507.02 1002.01 Dist. Lab/ Mat. Lab if failing or non-verif. material	Accept.*	Proj. Engr. S 201	1/transport or storage tank	2 gal Plastic bottle**	CD 1 & 8		5 days or 10 days if failing or non-verif. material	(QPL 41) *Send 1 gal to Mat. Lab for failing or nonverifying material. **Two one-gallon plastic bottles.
		507.02 1002.01 Mat. Lab	Accept.	•	1/type/ project**	1 gal Plastic bottle		2,000 yd²	10 days	(QPL 41) For complete analysis. *Shall be selected at random by the Dist. Lab from the acceptance samples submitted by the Proj. Engr. **Not required if sampled under another item.
	Rate of Application	507.06 Proj. Engr.	Accept.	Proj. Engr. 507.06(a)	1/each pass of distributor				1 day	