SECTION 306 SCARIFYING & COMPACTING ROADBED

MATERIAL		REF. / TESTED BY	PURP.	SAMPLED BY / METHOD	MIN. FREQ.	MIN. QUANT. / CONTAINER	CERT. / DISTR.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
EXISTING MATERIAL	Density	306.02 Proj. Engr.	Accept.	Proj. Engr. TR 401, TR415 or TR418	1/1000 lin ft/ 2-lane rdwy or 1/2000 lin ft/ shoulder	-----	-----	-----	½ hr.	-----
ASPHALTIC MATERIAL	Prime Coat	306.02	SEE SECTION 505 OF THIS MANUAL.							