SECTION 732 PLASTIC PAVEMENT MARKINGS

MATERIAL		REFERENCE / TESTED BY	PURP.	SAMPLED BY / METHOD	MIN. FREQ.	MIN. QUANT. / CONTAINER	CERT. / DISTR.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
BINDER-SEALER (Road Surface)		732.03(d)(1) Proj. Engr.	Accept.	-----	------	------	------	------	------	Visual inspection by Proj. Engr. to ensure that manufacturer recommendations are being followed.
GLASS BEADS		732.02(a) 1015.13 Mat. Lab.	Prelim. Source Approval	Dist. Lab or other state agencies	1/lot	1 - 50 lb bag	------	------	10 days	------
		732.02(a) 1015.13 Mat. Lab	Accept.	Proj. Engr. S 608	1/lot	1 - 50 lb bag	CD* 1 & 7	------	10 days	-----
PREFORMED PLASTIC MARKINGS (Cold Applied)		732.02(b) 1015.11 Mat. Lab	Accept.	Proj. Engr. S 609	1/lot	2 - 6 ft lengths*	------	------	10 days	*Coiled and placed in a gallon can.
THERMOPLASTIC MARKINGS (Hot Applied)		732.02(a) 1015.10 Mat. Lab	Prelim. Source Approval	Dist. Lab or other state agencies	1/lot	1 - 50 lb bag or block*	------	------	10 days	*Unless sampled at out- of- state facility.
		732.02(a) 1015.10 Mat. Lab	Accept.	Proj. Engr. S 610	1/lot	1 - 50 lb bag or block	CD 1 & 7	------	10 days	-----