SECTION 734 RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT

MATERIAL		REFERENCE / TESTED BY	PURP.	SAMPLED BY / METHOD	MIN. FREQ	MIN. QUANT. / CONTAINER	CERT. / DISTR.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
BACKFILL MATERIAL	Base Course Aggregate	1003.03	Accept.	Proj. Engr.	1/1000yd^3	1 full sample sack	-----	10 yd^3	4 days	-----
TEST PIT		734.03 Proj. Engr.	Accept.	Proj. Engr.	------	------	------	------	------	For purpose of approving equipment and pattern. Document in Field Book.