MATERIAL		REFERENCE / TESTED BY	PURP.	SAMPLED BY / METHOD	MIN. FREQ.	MIN. QUANT. / CONTAINER	CERT. / DISTR.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
BACKFILL	Reinforced Box Culverts	802.09(b) Proj. Engr.	Accept.	SEE SECTION 701 OF THIS MANUAL.						
	Structures Other Than Reinforced Box Culverts	802.09 Proj. Engr.	Accept.	------	------	------	------	------	------	Material shall be of acceptable quality and uniformly compacted by approved methods to the satisfaction of the Proj. Engr.
CONCRETE	Compressive Strength	802.09(e) Dist. Lab	*	Proj. Engr. S 301 TR 226	3 cyl/ location	2 ft^3 6 in. x 12 in. cylinder mold	------	------	10 days	*Used to determine earliest date for placement of backfill next to structures.