SECTION 803 SHEET PILES

| MATERIAL | | REFERENCE | PURP. | SAMPLED BY | MIN. FREQ. | MIN. QUANT. | CERT. | SMALL | TYPICAL HANDLING TIME | REMARKS (4.19) (A.19) |
|-------------------------------------|----------------------------------|--|--|---|--------------------------|-----------------|---------|-------|-----------------------------|---|
| | | TESTED BY | | METHOD | | CONTAINER | DISTR. | | | |
| HARDWARE | | 803.02 1018.08 Mat. Lab | Accept. | Proj. Engr. S 501 | 1/size/ type/shipment | 2 of each item* | | | 10 days | *Two pieces of each size and type of hardware used are to be submitted. |
| PAINT AND PROTECTIVE COATINGS | Coal Tar Epoxy | 803.02 803.06 1008.04 | SEE SECTION 811 OF THIS MANUAL. | | | | | | | |
| SHEET PILES | Aluminum or Steel | 803.02(b) 1013.10 Const. Fab. Insp. | Accept. | | | | CA 2 | | | |
| | Precast Concrete | 803.02(a) Const. Fab. Insp. | Accept. INSPECTED, APPROVED AND STAMPED BY CONST. FAB. INSP. PRIOR TO USE. SEE SECTION 805 OF THIS MANUAL. | | | | CD 1 | | | Visual inspection by Proj. Engr. |
| | Timber Treated & Untreated | 803.02(c) 1014 Const. Fab. Insp. | Accept. | CONST. FAB. INSP. PRIOR TO USE. SEE SECTION 812 OF THIS MANUAL. | | | | | | Visual inspection by Proj. Engr. |
| TREATMENT OF PILE HEADS | | 803.05 SEE SECTION 812 OF THIS MANUAL. | | | | | | | | |
| WELDING | | SEE SECTION 815 OF THIS MANUAL. | | | | | | | | |
| | | | | | | | | | | |
| | | | | | · | | | | | |