MATERIAL		REFERENCE / TESTED BY	PURP.	SAMPLED BY / METHOD	MIN. FREQ.	MIN. QUANTITY / CONTAINER	CERT. / DISTR.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
CONCRETE (Structural)	Mix Designs, Materials & Tests	814.02	SEE SECTION 901 OF THIS MANUAL.							
GRANULAR MATERIAL	Pea Gravel or Granular Material	814.02 1003.07	Accept.	------	------	------	------	------	------	Visual inspection by Proj. Engr.
REINFORCEMENT		814.02 1009 Mat. Lab*	Accept.	Proj. Engr. S 501	1/size/ source**	48 in. length	CA 1	-----	10 days	*Dist. Lab in Dist. 02. **If listed on QPL 71, material with a CA (Dist. 1) need not be sampled. Sample for verification if questionable.
SLURRY		814.12 Contractor	Quality Control	Contractor API 13B	As needed	------	------	------	------	------
		814.12 Proj. Engr.	Accept.	Proj. Engr.*	------	------	-----	------	------	*Contractor tests to be observed by the Proj. Engr. & documented in field book.