

TABLE OF CONTENTS

Topic	Page
Preface – Quality Assurance	xiii
Chapter 1 – Test Procedures	1
Table – 1	2
Chapter 2 – Certification	5
Plant.....	5
Plant Laboratory.....	7
Roadway Equipment.....	8
Personnel.....	9
Chapter 3 – Section 501 (Asphaltic Concrete Mixtures)	11
Mix Design Steps and Approval.....	11
1 – Material Procurement and Approval	11
Coarse Aggregate.....	11
Reclaimed Asphalt Pavement (RAP).....	12
Fine Aggregate	12
Asphalt Cement	12
Additives	13
2 – Aggregate Testing	13
Multi-Laboratory Precision for Bulk Specific Gravity (G_{sb})	13
Gradation	15
3 – Aggregate Blending	15
Figure 3-1 – Point 0.45 Power Curve with Coarse & Fine Sided Gradation ...	17
Figure 3-2 – Proposed JMF Gradation	
0.45 Power Curve with Control Points	18
4 – Trial Mix Blends	19
Figure 3-3 – Illustrating Bulk, Effective & Apparent Specific Gravities;	
Air Voids & Effective Asphalt Content in Compacted	
Asphalt Paving Mixtures	20
Figure 3-4 – Representation of Volumes in a Compacted Asphalt Specimen	
(Phase Diagram).....	21
5 – Optimum Asphalt Cement Content	24
Evaluation of VMA Curve.....	25
Effect of Air Voids	26
Effect of Voids Filled With Asphalt.....	26
6 – Moisture Sensitivity Analysis – Lottman Test (TSR).....	28
7 – Permeability Testing	28
8 – Submittal Process and Documentation (JMF Release Form).....	28
9 – Approval of JMF Proposal.....	29
10 – Validation of JMF Proposal	29
11 – Final Approval of JMF	31

TABLE OF CONTENTS

Topic	Page
Chapter 3 – Section 501 (Asphaltic Concrete Mixtures) - Continued	
QC Technician – Responsibilities	32
Gradation	32
Asphalt Cement Content.....	34
Laboratory Volumetrics	34
Additives	34
Temperature	34
Moisture	35
Documentation.....	36
DOTD Certified Technician – Responsibilities	37
Gradation (Extracted Gradation and Percent Crushed Aggregate) - Payment Factor Applied	38
Percent Crushed Aggregate and Percent Asphalt Cement	39
Asphalt Cement Properties – Payment Factor Applied.....	39
Percent Anti-Strip – Payment Factor Applied	39
Air Voids (Va), Voids in Mineral Aggregate (VMA), Marshall Stability & Flow	43
Maximum Theoretical Specific Gravity, G_{mm} – Rice Gravity	44
Moisture in Loose Mixture.....	44
Pavement Density.....	44
Surface Tolerance Requirements	49
Transverse Surface Tolerance	51
Cross Slope Tolerance	51
Grade Tolerance.....	51
Dimensional Requirements.....	52
DOTD District Laboratory Verification Responsibilities	52
Example Summary – Application of Payment Adjustments	53
Definition of a Lot	55
Application of a Lot Portion to Paving Operations	56
Provisions for Small Quantities	58
250 to 1000 Tons of HMA	58
Less than 250 Tons of HMA	58
Job Mix Formula Resubmittals.....	59
Summary of Documentation	60
Asphaltic Concrete Plant Certification Report.....	60
Certification Report for Scales and Meters	60
Asphaltic Concrete Paving Equipment Certification.....	60
Asphaltic Concrete Paving Equipment Checklist.....	60

TABLE OF CONTENTS

Topic	Page
Chapter 3 – Section 501 (Asphaltic Concrete Mixtures) - Continued	
Summary of Documentation – Continued	
Asphaltic Concrete Paving Miscellaneous Equipment Checklist	60
Job Mix Proposal (Release Form)	61
Asphaltic Concrete Gradation – 0.45 Power Curve	62
Mix Design Worksheet.....	62
Optimum Asphalt Cement Content – Summary of Test Properties	62
Tensile Strength Ratio (TSR).....	62
Asphaltic Concrete Plant Report.....	62
Asphaltic Concrete Control Charts.....	63
Asphaltic Concrete Pavement Report.....	63
Asphaltic Concrete Verification Report	64
Ticket for Hot Mix Asphalt	65
Chapter 4 – Section 502 (Superpave Asphaltic Concrete Mixtures) 67	
Mix Design Steps and Approval.....	67
1 – Material Procurement and Approval	67
Coarse Aggregate.....	67
Reclaimed Asphalt Pavement.....	68
Fine Aggregate	68
Asphalt Cement	68
Additives	69
2 – Aggregate Bulk Specific Gravity (G_{sb}) and Gradation	69
Bulk Specific Gravity (G_{sb})	69
Multi-Laboratory Precision For Bulk Specific Gravity (G_{sb})	70
Gradation	71
3 – Consensus Aggregate Test Evaluations.....	72
Coarse Aggregate Angularity (CAA)	72
Fine Aggregate Angularity (FAA).....	72
Flat and Elongated Count (FE)	73
Sand Equivalency (SE)	73
4 – Blending Aggregates to Meet Specified Gradation	74
Figure 4-1 - 0.45 Power Curve with Coarse and Fine Sided Gradations.....	75
5 – Trial Blends with Varying Asphalt Cement Contents	76
Figure 4-2 – Illustrating Bulk, Effective & Apparent Specific Gravities, Air Voids, & Effective Asphalt Content in Compacted Asphalt Paving Mixture	78
Figure 4-3 – Representation of Volumes in a Compacted Asphalt Specimen (Phase Diagram)	79

TABLE OF CONTENTS

Topic	Page
Chapter 4 – Section 502 (Superpave Asphaltic Concrete Mixtures) – Continued	
Superpave Definitions.....	80
6 – Selection of Optimum Asphalt Cement Content	83
Evaluation of VMA Curve.....	83
Effect of Air Voids	85
Effect of Voids Filled With Asphalt.....	85
7 – Dust to Effective Asphalt Cement Ratio Evaluation	86
8 – Moisture Sensitivity Analysis – Lottman Test (TSR).....	87
9 – Permeability Testing	87
10 – Submittal Process and Documentation (JMF Release Form).....	87
11 – Approval of JMF Proposal.....	89
12 – Validation of JMF Release Submittal	89
13 – Final Approval of JMF	91
QC Technician – Responsibilities	92
Gradation	92
Asphalt Cement Content.....	93
Laboratory Volumetrics (Payment Factor(s) Applied	94
Additives	94
Temperature	94
Moisture	95
Documentation.....	95
DOTD Certified Inspector – Responsibilities.....	97
Asphalt Cement Properties - Payment Factor Applied	97
Temperature	98
Percent Anti-Strip – Payment Factor Applied	98
Laboratory Volumetrics	101
Pavement Density.....	104
Surface Tolerance Requirements	108
Transverse Surface Tolerance	110
Cross Slope Tolerance	110
Grade Tolerance.....	110
Dimensional Requirements.....	111
DOTD District Laboratory – Verification Responsibilities.....	111
Example Summary – Application of Payment Adjustments	112
Definition of a Lot	113
Application of a Lot Portion to Paving Operations	116
Provisions for Small Quantities	117
250 to 1000 Tons of HMA.....	117
Less than 250 Tons of HMA	118

TABLE OF CONTENTS

Topic	Page
Chapter 4 – Section 502 (Superpave Asphaltic Concrete Mixtures) – Continued	
Job Mix Formula Resubmittals.....	119
Summary of Documentation	120
Asphaltic Concrete Plant Certification Report.....	120
Certification Report for Scales and Meters	120
Asphaltic Concrete Paving Equipment Certification.....	120
Asphaltic Concrete Paving Equipment Checklist.....	120
Asphaltic Concrete Paving Miscellaneous Equipment Checklist	120
Job Mix Proposal (Release Form)	121
Asphaltic Concrete Gradation – 0.45 Power Curve(s).....	122
Optimum Asphalt Cement Content – Summary of Test Properties	122
Tensile Strength Ration (TSR).....	122
Superpave Asphaltic Concrete Plant Report	122
Asphaltic Concrete Control Charts.....	123
Superpave Pavement Report	123
Asphaltic Concrete Verification Report	123
Ticket for Hot-Mix Asphalt.....	124
Chapter 5 – Section 508 (Stone Matrix Asphalt)	125
Mix Design Steps and Approval.....	125
1 – Material Procurement and Approval	125
Coarse Aggregate.....	126
Fine Aggregate	126
Asphalt Cement	126
Additives	127
2 – Aggregate Bulk Specific Gravity and Gradation.....	127
Bulk Specific Gravity (G_{sb})	127
Multi-laboratory Precision for Bulk Specific Gravity (G_{sb})	128
Gradation	128
3 – Blending Aggregates to Meet Specified Gradation	129
4 – Trial Blends with Varying Asphalt Cement Contents	130
SMA Terminology	132
Figure 5-1 – Illustrating Bulk, Effective & Apparent Specific Gravities, Air Voids & Effective Asphalt Content in Compacted Asphalt Paving Mixtures	133
Figure 5-2 – Representation of Volumes in a Compacted Asphalt Specimen (Phase Diagram).....	134
SMA Definitions	135
5 – Selection of Optimum Asphalt Cement Content	137
Evaluation of VMA Curve.....	138
Effect of Air Voids	139
Effect of Voids Filled With Asphalt.....	139

TABLE OF CONTENTS

Topic	Page
Chapter 5 – Section 508 (Stone Matrix Asphalt) - continued	
6 – Asphalt Cement Draindown Evaluation	140
7 – Moisture Sensitivity Analysis – Lottman Test (TSR)	140
8 – Submittal Process and Documentation - JMF Release Form	140
9 – Approval of JMF Proposal.....	142
10 – Validation of JMF Release Submittal.....	142
11 – Final Approval of JMF	143
 QC Certified Technician – Responsibilities	143
Testing Frequency	144
Marshall Designs	144
Superpave Gyratory Compactor Designs	145
Asphalt Cement Content.....	146
Laboratory Volumetrics	146
Additives	146
Temperature	147
Moisture	147
Documentation.....	148
 DOTD Certified Technician – Responsibilities	149
Asphalt Cement Properties – Payment Factor Applied.....	150
Percent Anti-Strip – Payment Factor Applied	150
Air Voids (V_a) and Voids in Mineral Aggregate (VMA) – Payment Factor Applied.....	153
Gradation - Payment Factor Applied.....	154
Pavement Density	156
Surface Tolerance Requirements	159
Transverse Surface Tolerance	161
Cross Slope Tolerance	161
Grade Tolerance.....	161
Dimensional Requirements.....	162
Asphalt Cement Draindown	162
Theoretical Maximum Specific Gravity (G_{mm}).....	162
 DOTD District Laboratory – Verification Responsibilities	162
Example Summary – Application of Payment Adjustments	163
Definition of a Lot	164
Application of a Lot Portion to Paving Operations	167
 SMA Compaction and MTV Requirements	168
Provisions for Small Quantities	168
Less than 250 Tons of SMA	168

TABLE OF CONTENTS

Topic	Page
Chapter 5 – Section 508 (Stone Matrix Asphalt) - continued	
Summary of Documentation	169
Asphaltic Concrete Plant Certification Report.....	169
Certification Report for Scales and Meters	169
Asphaltic Concrete Paving Equipment Certification.....	169
Asphaltic Concrete Paving Equipment Checklist.....	169
Asphaltic Concrete Paving Miscellaneous Equipment Checklist	169
Job Mix Proposal (Release Form)	170
Asphaltic Concrete Gradation – 0.45 Power Curve	171
Optimum Asphalt Cement Content – Summary of Test Properties	171
Tensile Strength Ratio (TSR).....	171
Asphaltic Concrete Plant Report.....	170
Asphaltic Concrete Control Charts.....	172
Pavement Report.....	172
Asphaltic Concrete Verification Report	173
Ticket for Hot-Mix Asphalt.....	174
 Chapter 6 – HMA Inspection (QC Technician and DOTD Inspector) 175	
Plant Inspection	176
Stockpiles and Handling	176
Cold Bins	176
Plant Equipment	177
Scales and Meters	178
HMA Mixtures	179
Temperature of the HMA Mixture.....	179
Segregation	179
Uniformity.....	179
Color (Odor).....	179
Asphalt Coating	179
Moisture	179
Haul Trucks.....	180
Paving Inspection.....	180
Paving Equipment.....	180
Traffic Control	182
Surface Preparation.....	182
Tack Coat	182
Prime Coat.....	183
Curing Membrane	184
HMA Mixtures	184
Paving Operations	185
Coordination of Paving Operation with Production and Transport.....	185
Determination of Optimum Paver Speed based on Truck Arrivals	186

TABLE OF CONTENTS

Topic	Page
Chapter 6 – HMA Inspection (QC Technician and DOTD Inspector), Continued	
Determination of Optimum Paver Speed based on Plant Production	188
Yield.....	190
Theoretical Yield	190
Actual Yield.....	192
Joint Construction	193
Transverse Joints	193
Transverse Joint Inspection for Approval	194
Longitudinal Joints	195
Segregation.....	196
Paver Operation.....	198
Roller Operation (Compaction)	198
Weather Limitations	201

TABLE OF CONTENTS - APPENDIX

Topic	Page
Asphaltic Concrete Plant Certification Report.....	A-1
ABSON Recovery of HMAC.....	A-9
HMA Plant Certification Sticker.....	A-11
Certification Report for Scales and Meters	A-13
Asphaltic Concrete Paving Equipment Certification – Distributor.....	A-15
Asphaltic Concrete Paving Equipment Certification – Paver	A-17
Asphaltic Concrete Paving Equipment Certification – Compaction Equipment	A-19
Equipment Certification Sticker with 90 Day Inspection Sticker.....	A-21
Asphaltic Concrete Paving Equipment Checklist	A-23
Asphaltic Concrete Haul Truck	A-25
EDSM III.1.1.12 – Enforcement of Legal Load Requirements	A-27
Truck Weight Certification Sticker.....	A-43
Sample Identification Form	A-45
Aggregate Test Report Form (2 pages)	A-47
Certificate of Delivery for Asphaltic Materials	A-49
Certificate of Delivery for Anti-strip Additives.....	A-51
Asphaltic Concrete Mix Design Worksheet.....	A-53
Asphaltic Concrete Gradation 0.45 Power Curve – ½" NMS	A-55
Asphaltic Concrete Gradation 0.45 Power Curve – ¾" NMS	A-57
Asphaltic Concrete Gradation 0.45 Power Curve – 1" NMS	A-59
Optimum Asphaltic Cement Content – Summary of Test Properties.....	A-61
Tensile Strength Ratio (TSR) – Lottman Test	A-63
Asphaltic Concrete Job Mix Formula Form – Section 501	A-65
Asphaltic Concrete Job Mix Formula Form – Section 501 – Proposal.....	A-66
Asphaltic Concrete Job Mix Formula Form – Section 501 – Validation	A-67
Asphaltic Concrete Plant Report – Section 501	A-69
Asphaltic Concrete Control Charts.....	A-71
Asphaltic Concrete Pavement Report – 2000 Specifications.....	A-73
Asphaltic Concrete Verification Report – 2000 Specifications	A-75
Asphalt Cement Submittal Form	A-77
Performance Graded Asphalt Binder Submittal Form.....	A-78
Correction Factor for JMF (DOTD TR 323 – Ignition Oven)	A-79
Moisture Content of Asphaltic Concrete (Loose Mix – DOTD TR 319).....	A-81
DOTD Superpave Quality Level Analysis Specifications	A-83
Louisiana Superpave JMF Form	A-99
Louisiana Superpave JMF Form – QPAVE Version	A-100
Louisiana Superpave JMF Form – Contractor Example	A-101
Louisiana Superpave Proposed Aggregate Blend and Volumetric Results	A-102
Louisiana Superpave Proposed Aggregate Blend Plot–0.45 Power Curve	A-103
Louisiana Superpave Proposed Blend Volumetric Summary	A-104
Louisiana Superpave–Summary of Test Properties	A-105
Louisiana Superpave–Summary of Test Properties – Example	A-106
Coarse Aggregate Angularity Test Results.....	A-107
Fine Aggregate Angularity Test Results	A-108

TABLE OF CONTENTS - APPENDIX

Topic	Page
Flat and Elongated Test Results	A-109
Sand Equivalency Test Results	A-110
Superpave Gyratory Printout Results for Proposed Optimum Blend	A-111
Superpave Quality Level Analysis	A-113
Superpave Plant Report – Section 502 – QA –QPAVE	A-115
Superpave Plant Report – Section 502 – QC –QPAVE.....	A-116
Superpave Asphaltic Concrete Roadway Report	A-117
Louisiana Superpave Aggregates.....	A-119
Superpave Asphaltic Verification Report	A-121